# BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE
## Office of the Executive Engineer, Dasarahalli Division
Schedule-B

NAME OF THE WORK: Construction of RCC drains near Aswathkatte Surrounding area roads and 4th A, B, C, D, E cross all sides Shettyhalli Sub Division, in Ward No.13.

| Sl. No | Description of work | Unit | Qty | Approved Sanctiioned Rate | |
|---|---|---|---|---|---|
| | | | | In Figures (Rs.) | In Words (Rs.) |
| 1 | 2 | 3 | 4 | 5 | 6 |
| 1 | KSRRB 300-3. Earthwork excavation by manual means in ordinary soil invoiving in average horizontal throw up to 2m & an average lift upto 1.5m , excavated surface leveled & sides neatly dressed , the disposed earth to be levelled neatly after breaking of clods complete as per specification MORTH/ Chapter 3. Page No. 141/ Item No. 19.1/ PWD SR 2015-16 | Cum | 518.94 | 83.16 | Rupees Eighty Three and Sixteen Paise Only |
| 2 | KSRB 4-1.3 : Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.3 Page No.12/ Item No. 4.3/ PWD SR 2015-16 | Cum | 88.97 | 5070.60 | Rupees Five Thousand Seventy and Sixty Paise Only |
| 3 | KSRB 4.2.2 : Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320kgs, with with 20mm and down size graded granite metal, coarse aggregate @ 0.69 cum and fine aggregates @ .460cum, with super plasticisers @ 3 liters confirming to is 9103-1999 reafairmed -2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation for footings,pedastals,retaining walls, staircase, retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing, complete as per specifications. Specification No. KBS 4.1, 4.5 ,P.13/I.4.11/ PWD SR 2015-16 | Cum | 279.54 | 6198.12 | Rupees Six Thousand One Hundred Ninety Eight and Twelve Paise Only |

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010
Signature of the Contractor

Executive Engineer
Dasarahalli Division

| | | | | | |
|---|---|---|---|---|---|
| 4 | KSRB 4.9.2: Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.Specification No. KBS 4.6.3, TMT bars Fe 500. Page No. 17/ Item No. 4.46.2/ PWD SR 2015-16 | Qtls | 167.72 | 6980.58 | Rupees Six Thousand Nine Hundred Eighty and Fifty Eight Paise Only |
| 5 | KSRB 4-6.9: Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walss at any thickness,including attached pilasters,buttresses, plinth and string courses cost of all materials, labour complete as per specification. Specification No. KSRB 4.6.9. exceeding 1m in depth. Page No. 15/ Item No. 4.31/ PWD SR 2015-16 | Sqm | 2622.20 | 306.72 | Rupees Three Hundred Six and Seventy Two Paise Only |
| 6 | Providing & laying reinforeced cement precast slabs of mix CC 1:11/2:3 using 20mm & down size graded Granite metal using HYSD 10mm dia steel @ 100mm c/c both ways & Complete as per specfications. | Cum | 153.90 | 1600.00 | Rupees One Thousand Six Hundred Only |
| 7 | Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 10 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading Item No. 17.1 KSRRB M 100-1 Rs. 68.00 (P.133 I.18.57/1) 2015-16 | Cum | 518.94 | 81.73 | Rupees Eighty One and Seventy Three Paise Only |

Signature of the Contractor

EXECUTIVE ENGINEER
DASA, BBMP DIVISION
BENGALURU-560 010

Executive Engineer,
Dasarahalli Division,

Signature of the Contractor

Executive Engineer
Dasarahalli Division